Economic Development & Industrial Corporation of Boston ("EDIC")
d/b/a Boston Planning & Development Agency ("BPDA")

"Pier 10 Upgrades and Floating Dock"
INVITATION FOR BID ("IFB")

Boston Planning & Development Agency
One City Hall Square, Room 900A/Reception
Boston, MA 02201-1007

ADDENDUM NO. 6 dated February 12, 2024

This addendum modifies, revises, amends, and supplements designated parts of the **"Pier 10 Upgrades and Floating Dock" INVITATION FOR BID ("IFB")** issued on **January 1, 2024** and is hereby made a part thereof by reference and shall be as binding as though inserted in its entirety in the locations designated hereunder.

Wherever portions of any addendum conflict with a previous addendum, the addendum bearing the latest date shall govern. It shall be the responsibility of each consultant to notify all sub-consultants of any changes or modifications contained in this addendum. No claim for additional compensation due to the lack of knowledge of the contents of this addendum will be considered. Consultant(s) are hereby notified they must acknowledge this addendum as part of the IFB submission requirements.

General

Item 1: The following questions were received in writing by the date and time specified in additional question and answer period as specified in Addendum 5 and the response is as follows:

Q1: Please confirm painting requirements for inside of the new steel float.

> **A1:** The interior coating system shall be similar to the exterior of the float except per specification 09 80 00 – Coatings, Section 2.01. C, Coating on the interior of all steel floating dock units shall be a high solids epoxy (white).

Q2: Please confirm the "SECTION 03 31 32 PUMPED/TREMIE CONCRETE" specification (issued in Addendum 4) concrete material is to be used for the pile jacket repair infill.

> **A2:** The referenced specification is for pile jacket repair as a concrete specification option. Repair grout is also approved as specified in the original bid package.

Q3: Please confirm if there is an electrical specification to address what type of lighting will be required as noted in Addendum 3 drawings.

> **A3:** There will be no electrical specification, the gangway lighting and platform lights shall be recommended by the manufacturer to provide adequate lighting for passengers loading and unloading for the vessels.

Q4: Please confirm a fencing specification.

> **A4:** The fencing shall be similar to the existing fence with steel coated tube and wire rope. Similar fencing can be found in the reference drawings.

Q5: Would you consider (permit permitting) coring holes in the deck and driving new piles to support the deck in lieu of the pile jackets.

> **A5:** This option will not be considered due to required change to existing approved permit.

Q6: Please confirm the final freeboard is 4'-0" to top of deck per drawing scale in order to calculate and estimate ballast properly.

> **A6:** Confirmed.

Tim Mathis
Interim Director of Finance/Chief Procurement Officer
END OF ADDENDUM 6